

Middle Fork Creek Excavating Co

16739 Akin Blacktop

Benton, IL 62812 US

+1 6189275505

middleforkcreekexcavating04@outlook.com

www.middleforkcreekexcavatingco.com

Estimate**ADDRESS**

Franklin County Animal Control
 13163 Oddfellow Lane
 Benton, IL 62812

ESTIMATE #	DATE
1182	08/14/2024

DATE	DESCRIPTION	QTY	RATE	AMOUNT
	Bobcat T-770			
	-7ft Bucket			
	Case CX55B			
	-18in Bucket			
	Ford Single Axle Dump Truck			
	Materials Needed			
	-320ft of 8in SR35 Pvc pipe			
	-30ft of 4in SR35 pipe			
	-4 4in 90 degree			
	-4 4in gutter connectors			
	-2 3in Trough drains			
	-1 8in cap			
	-1 8in 22 bend			
	-4 8inx4in Ts			
	-Glue and Cleaner			
	Laborer and Tools			
	Total Cost of Job			9,235.00

Job Description: We are installing an 8in drainage pipe on the West side of the dog pound building. We will connect all of the gutters on the West side of the building using 4in sr35 pipe. The pipe will be used to drain the water to the North of the building next to the other drainage pipes. We are also going to install 2 trough drains against the concrete to catch any water running towards the building. We will need to remove the parking curbs, and we will place them back once the project is complete. The pipe will be back filled with ca-6 rock supplied by the FCHD.

TOTAL**\$9,235.00**

Accepted By

Accepted Date

We appreciate your business and look forward to helping you again soon.
 Andrew 618.927.9134 or Austin 618.927.7116